


1 GROUND FLOOR TELECOMMUNICATIONS PLAN - SHEET 6
SCALE: 1/4" = 1'-0"

- GENERAL NOTES:**
- 1 PROVIDE 1" CONDUIT FROM ALL TELECOM DEVICES (VOICE, DATA, AND WAP) TO THE NEAREST CABLE TRAY. HOMERUN CABLES TO TO ITS DESIGNATED FLOOR TELECOM ROOM. SEE DETAIL T6.3
 - 2 STUB-UP 1" EMPTY CONDUIT WITH PULLSTRINGS FROM ALL CCTV JUNCTION BOX AND SPEAKER JUNCTION BOX TO THE NEAREST CABLE TRAY.

NOTES: (LIST OF NOTES APPLICABLE TO ALL T4.X.X SERIES DRAWINGS. NOT ALL NOTES MAY BE USED ON EACH INDIVIDUAL T4.X.X DRAWINGS)

- 1 STATEGICALLY LOCATE DEVICE SO THEY ARE INSTALLED BEHIND THE TV MONITOR (HIDDEN FROM VIEW) COORDINATE WITH TV MONITOR INSTALLATION.
- 2 MOUNT 8" ABOVE COUNTER.
- 3 PROVIDE ESS REQUIREMENT FOR SINGLE DOOR DETAIL, SEE T6.6
- 4 PROVIDE ESS REQUIREMENT FOR DOUBLE DOOR DETAIL, SEE T6.6
- 5 FLOOR MOUNTED JUNCTION BOX STUB-UP TO NEAREST CABLE TRAY FOR FUTURE RFID.
- 6 MOUNT AT 10'-0" AFF.
- 7 MOUNT 2" ABOVE COUNTERTOP TO BOTTOM OF TELECOM OUTLET.
- 8 FOR TELECOMMUNICATION EQUIPMENT ELEVATIONS, SEE T2.4
- 9 HOMERUN 1" EMPTY CONDUIT WITH PULLSTRINGS FROM ALL AV JUNCTION BOX AND SPEAKER JUNCTION BOX TO MEDIA STORAGE 301b JUNCTION BOX.
- 10 6-GANG X 2-1/2"D LARGE AV BOX.
- 11 MOUNT 10'-0" AFF.



IF SHEET IS LESS THAN 24" X 36"
REDUCED PRINT - USE GRAPHIC SCALES

REVISIONS		
No.	Description	Date
1	ADDENDUM 1	12/6/22

TRMA

Taniguchi Ruth Makio Architects
100 Cliff Business Center, P.O. Box EA, Agaña, GU 96910
Tel.: (671) 475-8772 • Fax.: (671) 472-3381

Architecture
Planning
Interior Design

eme

EMCE - Consulting Engineers
SUITE 201, 133 ANTONIA COURT
P.O. BOX 9940 TAMUNING, GUAM 96931
671. 649-0166/7 Phone
671. 646-EMCE (3623) Fax



Project:

NMC
PACKAGE 1: STUDENT
CENTER BUILDING

Title:

GROUND FLOOR
TELECOMMUNICATIONS
PLAN - SHEET 6

CONSTRUCTION
DOCUMENTS

Designed: JF/LB
Drawn: NP/RS
Checked: IA/AM
Supv: AM
Scale: AS INDICATED
Date: 10/07/2022
Project No. 24-22-493
Drawing No.

T4.1.6

Sheet No. of