



1 GROUND FLOOR TELECOMMUNICATIONS PLAN - SHEET 7
SCALE: 1/4" = 1'-0"

GENERAL NOTES:

- 1 PROVIDE 1" CONDUIT FROM ALL TELECOM DEVICES (VOICE, DATA, AND WAP) TO THE NEAREST CABLE TRAY. HOMERUN CABLES TO TO ITS DESIGNATED FLOOR TELECOM ROOM. SEE DETAIL T6.3
- 2 STUB-UP 1" EMPTY CONDUIT WITH PULLSTRINGS FROM ALL CCTV JUNCTION BOX AND SPEAKER JUNCTION BOX TO THE NEAREST CABLE TRAY.

NOTES: (LIST OF NOTES APPLICABLE TO ALL T4.X.X SERIES DRAWINGS. NOT ALL NOTES MAY BE USED ON EACH INDIVIDUAL T4.X.X DRAWINGS)

- 3 STATEGICALLY LOCATE DEVICE SO THEY ARE INSTALLED BEHIND THE TV MONITOR (HIDDEN FROM VIEW) COORDINATE WITH TV MONITOR INSTALLATION.
- 4 MOUNT 8" ABOVE COUNTER.
- 5 PROVIDE ESS REQUIREMENT FOR SINGLE DOOR DETAIL, SEE T6.6
- 6 PROVIDE ESS REQUIREMENT FOR DOUBLE DOOR DETAIL, SEE T6.6
- 7 FLOOR MOUNTED JUNCTION BOX STUB-UP TO NEAREST CABLE TRAY FOR FUTURE RFID.
- 8 MOUNT AT 10'-0" AFF.
- 9 MOUNT 2" ABOVE COUNTERTOP TO BOTTOM OF TELECOM OUTLET.
- 10 FOR TELECOMMUNICATION EQUIPMENT ELEVATIONS, SEE T2.5
- 11 HOMERUN 1" EMPTY CONDUIT WITH PULLSTRINGS FROM ALL AV JUNCTION BOX AND SPEAKER JUNCTION BOX TO MEDIA STORAGE 301b JUNCTION BOX.
- 12 6-GANG X 2-1/2"D LARGE AV BOX.
- 13 MOUNT 10'-0" AFF.




Project: NMC
PACKAGE 1: STUDENT CENTER BUILDING

Title: GROUND FLOOR TELECOMMUNICATIONS PLAN - SHEET 7
CONSTRUCTION DOCUMENTS

Designed: JF/LB
Drawn: NP/RS
Checked: IA/AM
Supv: AM
Scale: AS INDICATED
Date: 10/07/2022
Project No. 24-22-493
File
Drawing No.

T4.1.7
Sheet No. of



IF SHEET IS LESS THAN 24" X 36"
REDUCED PRINT - USE GRAPHIC SCALES