


1 AUDIO VISUAL (AV) INFRASTRUCTURE AT MULTI-PURPOSE RM. 302b and BOR 311a  
NOT TO SCALE



2 AUDIO VISUAL (AV) INFRASTRUCTURE AT MULTI-PURPOSE EVENT ROOM  
NOT TO SCALE

GENERAL NOTES:



- 1 ALL AV AND TELECOMMUNICATIONS EQUIPMENT/OUTLETS/BOXES BEHIND AV CREDENZA MUST BE INSTALLED 18"MIN AFF TO THE CENTER OF THE BOX UNLESS OTHERWISE NOTED.
- 2 ALL CONDUIT ROUTING IS NOTIONAL.
- 3 ALL CONDUIT MUST BE 1" MINIMUM WITH PULL STRINGS UNLESS OTHERWISE NOTED.
- 4 ALL CONDUIT MUST BE CONCEALED IN WALL OR IN CONCRETE SLAB.
- 5 ALL AV BOXES MUST BE 4 11/16" SQUARE BY 2 1/8" DEEP AND MUST BE FLUSHED MOUNTED.
- 6 ALL AV BOXES MUST BE INSTALLED WITH A DOUBLE GANG ADAPTER PLATE.
- 7 ALL DUPLEX AND QUADRUPLX RECEPTACLES AND DATA OUTLET MUST BE INSTALLED VERTICALLY.
- 8 AV CREDENZA DISPLAY, DISPLAY WALL MOUNT, DISPLAY PLYWOOD BACKBOARD AND VTC CAMERA ARE SHOWN FOR REFERENCE ONLY.
- 9 JUNCTION BOXES MUST BE 4 11/16" SQUARE X 2 1/8" DEEP AND INSTALLED WITH BLANK COVER PLATE.

GENERAL NOTES:

- 1 ALL AV AND TELECOMMUNICATIONS EQUIPMENT/OUTLETS/BOXES BEHIND AV CREDENZA MUST BE INSTALLED 18"MIN AFF TO THE CENTER OF THE BOX UNLESS OTHERWISE NOTED.
- 2 ALL CONDUIT ROUTING IS NOTIONAL.
- 3 ALL CONDUIT MUST BE 1" MINIMUM WITH PULL STRINGS UNLESS OTHERWISE NOTED.
- 4 ALL CONDUIT MUST BE CONCEALED IN WALL OR IN CONCRETE SLAB.
- 5 ALL AV BOXES MUST BE 4 11/16" SQUARE BY 2 1/8" DEEP AND MUST BE FLUSHED MOUNTED.

NOTE:

- ◇ 6-GANG X 2-1/2"D LARGE AV BOX.



Project:	
NMC	
PACKAGE 1: STUDENT CENTER BUILDING	
Title:	
TELECOMMUNICATIONS DETAILS - SHEET 7	
CONSTRUCTION DOCUMENTS	
Designed:	JF/LB
Drawn:	NP/RS
Checked:	IA/AM
Supv:	AM
Scale:	AS INDICATED
Date:	10/07/2022
Project No.	File
Drawing No.	T6.7
Sheet No.	of