


- GENERAL NOTES:
- 1 ALL EQUIPMENT CABINETS MUST BE ANCHORED TO FLOOR USING APPROVED MATERIALS AND METHODS.
 - 2 CONTRACTOR MUST INSTALL, TERMINATE AND TEST ALL SIGNAL, POWER AND GROUND CABLES AS PER CONTRACT.
 - 3 NEATLY BUNDLE (DRESS CABLES LONGITUDINALLY) AND SUPPORT (USING FASTENERS AND TIES) TELECOMMUNICATIONS CABLES ONTO CABLE TRAY. NEATLY BUNDLE AND SUPPORT TELECOMMUNICATIONS CABLES ONTO VERTICALLY MOUNTED CABLE RUNWAY WHEN RISING FROM FLOOR SLEEVES OR DESCENDING FROM CEILING SLEEVES USING APPROVED TIES. NEATLY BUNDLE TELECOMMUNICATIONS CABLE ONTO THE BACK OF THE VERTICAL CABLE MANAGEMENT SECTION USING APPROVED TIES. DRESS TELECOMMUNICATIONS CABLE FROM THE VERTICAL MANAGEMENT SECTIONS TO THE TERMINATION POSITION.
 - 4 ALL PATCH CORDS MUST BE LABELED ON EACH END (APPROXIMATELY 3" FROM CONNECTOR)
 - 5 ALL PATCH PANELS MUST BE LABELED USING ANSI/TIA/EIA-606 LABELING SCHEME.
 - 6 PROVIDE RADIUS DROPOUTS WHERE CABLES TRANSITION DOWNWARD FROM OVERHEAD HORIZONTAL CABLE TRAY.
- NOTE:
◆ TELECOMMUNICATIONS CABINET. FOR ADDITIONAL REQUIREMENTS. SEE SHEET 1 T6.5



Project:
NMC
PACKAGE 1: STUDENT
CENTER BUILDING

Title:
TELECOMMUNICATIONS
CABINET ELEVATIONS
- SHEET 3
CONSTRUCTION
DOCUMENTS

Designed: JF/LB
Drawn: NP/RS
Checked: IA/AM
Supv: AM
Scale: AS INDICATED
Date: 10/07/2022
Project No. File

Drawing No.
T2.3
Sheet No. of

IF SHEET IS LESS THAN 24" X 36"
REDUCED PRINT - USE GRAPHIC SCALES