



1 THIRD FLOOR TELECOMMUNICATIONS PLAN - SHEET 6
SCALE: 1/4" = 1'-0"

GENERAL NOTES:

- 1 PROVIDE 1" CONDUIT FROM ALL TELECOM DEVICES (VOICE, DATA, AND WAP) TO THE NEAREST CABLE TRAY. HOMERUN CABLES TO TO ITS DESIGNATED FLOOR TELECOM ROOM. SEE DETAIL (1 T6.3)
- 2 STUB-UP 1" EMPTY CONDUIT WITH PULLSTRINGS FROM ALL CCTV JUNCTION BOX AND SPEAKER JUNCTION BOX TO THE NEAREST CABLE TRAY.

NOTES: (LIST OF NOTES APPLICABLE TO ALL T4.X.X SERIES DRAWINGS. NOT ALL NOTES MAY BE USED ON EACH INDIVIDUAL T4.X.X DRAWINGS)

- ◇ STATEGICALLY LOCATE DEVICE SO THEY ARE INSTALLED BEHIND THE TV MONITOR (HIDDEN FROM VIEW) COORDINATE WITH TV MONITOR INSTALLATION.
- ◇ MOUNT 8" ABOVE COUNTER.
- ◇ PROVIDE ESS REQUIREMENT FOR SINGLE DOOR DETAIL, SEE (1 T6.6)
- ◇ PROVIDE ESS REQUIREMENT FOR DOUBLE DOOR DETAIL, SEE (2 T6.6)
- ◇ FLOOR MOUNTED JUNCTION BOX STUB-UP TO NEAREST CABLE TRAY FOR FUTURE RFID.
- ◇ MOUNT AT 10'-0" AFF.
- ◇ MOUNT 2" ABOVE COUNTERTOP TO BOTTOM OF TELECOM OUTLET.
- ◇ FOR TELECOMMUNICATION EQUIPMENT ELEVATIONS, SEE (1 T2.5)
- ◇ HOMERUN 1" EMPTY CONDUIT WITH PULLSTRINGS FROM ALL AV JUNCTION BOX AND SPEAKER JUNCTION BOX TO MEDIA STORAGE JUNCTION BOX.
- ◇ 6-GANG X 2-1/2"D LARGE AV BOX.
- ◇ MOUNT 10'-0" AFF.



Project: NMC
PACKAGE 1: STUDENT CENTER BUILDING

Title: THIRD FLOOR TELECOMMUNICATIONS PLAN - SHEET 6
CONSTRUCTION DOCUMENTS

Designed: JF/LB
Drawn: NP/RS
Checked: IA/AM
Supv: AM
Scale: AS INDICATED
Date: 10/07/2022
Project No. 24-22-493
File
Drawing No.

T4.3.6
Sheet No. of